ENGINEERING DEPARTMENT.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER, GOVERNMENT OF MYSORE.

Notice dated September 1921.

Tenders for the purchase of the following are invited so as to reach the undersigned on or before the 20th October 1921.

(1) Five tons of copper scrap.

(Samples to be had for inspection at the Central Stores, "C. P. S." near Messrs. Binny's Mills, Bangalore.)

Each tender to be accompanied with an earnest money of Rs. 100 to be remitted separately which will either be refunded or adjusted towards the value of the materials purchased as the case may be.

TERMS.

1. The quantities noted above are only approximate and the actual may be either more or less. Tenders may be for any part or whole of any or all items.

2. Tenders will be opened at noon on the 21st October 1921; acceptance or otherwise of the tenders will be notified as early as possible after the above date.

3. Twenty-five per cent of the purchase money should be paid immediately on intimation of acceptance of the tender and the balance at the time of taking delivery; failure to do which will entail forfeiture of the earnest money and render the tender liable to be rejected.

4. The delivery of the material will commence within a week after the deposit of the 25 per cent of the purchase money and complete delivery in one month thereafter.

5. The undersigned reserves the right to reject any or all tenders without assigning any reasons nor does he bind himself to sell to the highest bidder.

6. Delivery at our Central Stores above referred to.

Packing and loading actuals extra.

S. G. FORBES,
Chief Electrical Engineer.

MYSORE DISTRICT.

Dated 25th September 1921.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 12 noon on the 25th October 1921 for constructing V. E. School at Agrahar, Batchalli in Krishnarajpete Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1922.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. to 4 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing A. V. School at Agrahar, Batchalli, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

10. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract of quantities for constructing the V. E. School at Agrahar, Batchalli in Krishnarajpete Taluk.

No.	Names of items	Unit	Quantity
1	Clearing site and levelling the ground	Lump sum	
2	Earthwork excavation	100 c. ft.	1[illegible]36
3	Burnt brick in clay	"	32·71
4	Burnt brick in chunam	"	253
5	Chunam plastering	100 s. ft.	48·56
6	Burnt stone slabs, dressed and fixed	S. ft.	258
7	White and colourwashing	100 s. ft.	46·56
8	Honnewood work, wrought and putlup	C. ft.	81·57
9	Roofing with 1st class Mangalore tiles on teak reepers, complete	100 c. ft.	16·83
10	Mangalore ridge tiles set in mortar	R. ft.	55
11	Chunam borders	"	108
12	Cutting grooves in stone, uprights	Each	8
13	Coping with burnt brick in chunam plastering	R. ft.	53
14	Capitals to gate pillars	Each	2
15	Flooring with gravel including cowdung washing	C. yd.	25
16	Honnewood battoned doors, planks 1½" thick including frames 4" x 3", hinges, etc., complete.	S. ft.	98
17	Honne wood battened windows with iron bars ½" diameter, complete	"	81
18	Mangalore ventilating tiles	Each	8
19	Painting with chocolate	Sqr.	9·83
20	Wood oiling (2 coats)	"	7·51
21	Honnewood gate shutters including iron works and painting, etc.	S. ft.	22
22	Providing black board	Each	2

K. V. KARVE, *Executive Engineer.*

CHITALDRUG DIVISION.

FORM OF ADVERTISEMENT.

Dated October 1921.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 31st October 1921, for restoring Yelagodu minor tank in Chitaldrug Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should completed by the end of 15th June 1922.

2. The plans, detailed estimate and conditions may seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 4 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 (rupees one hundred only) in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring Yelagodu minor tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will vest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for restoring Yelagodu minor tank in Chitaldrug Taluk.

No.	Items of work	Unit	Quantity
	Bund—		
1	Earthwork to bund with watering, etc., complete	C. yd.	6,468
2	Removing and resetting old revetment with new jelly	"	506
3	Jungle clearing over bund	L. S.	Rs.
4	Providing and fixing gauge stone	No.	1
5	Do do Register No. and date stone	"	1
6	Do do new grade stones	"	18
7	Cutting figures, etc., and refixing old grade stones	"	26
8	Providing new top width stones	"	44
9	Painting and fixing B. M. stones	L. S	Rs.
10	New rough stone revetment	C. yd.	319
	Sluice—		
1	Cutting open the bund and examining the leak in the tunnel and repairing and refilling the gap with available earth	L. S.	Rs.
	Weir—		
1	Plastering with cement	Sq.	3

S. A. RAMASWAMI IYER, *Executive Engineer.*